BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Name of Work :-Removal of Debris & Disilting of Drains in Dasarahalli Ward No 15

Sl	Description of Item	Unit	Est. Cost Rs No	L	B	D	20.00 Qty	Lakhs Rate	Lakhs Amount
1	Supply of the Labour Heavy Mazdoor to the required place as per the direction of the engineer in charge Complete as per Specification, and as per direction of Engineer-in charge. Page No LVI Sl No 5 PWD SR 2018-19								
	26 Daysx4 Month=104	Days	26	4	104	20	2080.00		
	per day 20 Mazdoor 104x20=2080								
							2080.00	446.20	928096.00
2	Tractor 50 HP on hire basis including Tractor Driver with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the work (PWD SR 2018-19, P-XLVIII, It.No.20)							Days	
	2x26 Daysx4 Month=208	Days	26	4	2		208.00		
	per day 2 Tractor								
	Emergency Tractor required		12		1		12.00		
							220.00	2129.00	468380.00
	J.C.B. Excavator on hire basis including JCB Operator with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the work (PWD SR 2018-19, P-XLVIII, It.No.23)							Days	
	20 Days x 1No	Days	10	1			10.00	5695.00	56950.00
	Removing and resetting of kerb stones(PWD SR 2018-19, Page No.270, Item No.37.57)							Sqm	
	t Selected Roads	Sqm	1	725.00	0.90		652.50		
							652.50	208.82	136255.00
	Basic Rate	197.00							
	Add Area Weightage 6%	11.82							
	Total	208.82							
	pplying and fixing precast rainforced concrete slab 10cm thick luding cost of reinforcement as per design and drawing material cost, nsportation, hire charges of machinery, machine cutting the vertical to get plain even surface stc., complete with all leads and lift veyance charges, labour charges inclusive of cost of all materials.								
	For New Slab	Sqm	1	52.92	0.90		47.63		
	Rates Approved by CE DZ enclosed						47.63	2208.00	105163.00

Scanned by CamScanner

Sub Total		1694844.00
		84742.00
		203381.00
		16948.00
		85.00
Total		2000000.00

(Rupees. Twenty Lakhs Only)

Assistant Engineer
Ward-15

Assistant Executive Engineer
T. Dasarahalli Sub-Division
B.B.M.P

Executive Engineer
Dasarahalli Division
B.B.M.P. Bangalore.

ನಂ. EE/DD/AS/123/19-20 ದಿನಾಂಕ :

ರೂ. ಇಪ್ಪತ್ತು ಲಕ್ಷ

Rupees Twenty Lakhs Only

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂ.ಮ.ನಿ.ಪ.

ನಂ. EE/DD/TS/58/18-19 ದಿನಾಂಕ : 30/01/2019

ರೂ. Rs. 20.00 lakhs/- (Rs Twenty lakhs only)

ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

Scanned by CamScanner